

HARYANA IRRIGATION & WR DEPARTMENT

NOTICE INVITING SEALED QUOTATION ON EMERGENT BASIS

Sealed quotations are invited by the Executive Engineer, Construction Division No.31, Gurugram office situated at office of Executive Engineer, Construction Division No.31, Canal Colony, Gate No.1, Sector-16, Gurugram for the work of "Topographical Survey work of Mewat Feeder Canal Project off-taking from GWS Canal (50.600KM)" through private agency on emergent basis, details as tabulated below:-

| S No. | Name of Work | Length in KM | Width in Mtr | Scope of work | Date and time | Earnest Money | Period of completion |
|--------------|--|---------------------|--|--|--|----------------------|-----------------------------|
| 1 | Topographical Survey for Mewat Feeder Canal Project off-taking from GWS Canal(50.600KM) along KMP Expressway (Right side) to near Nuh Disty.,at Khor Basai | 50.500 | 25 Mtr in consultation with Engineer-in-charge | Observing & plotting of L-sections, X-sections & topography of MFC including existing structure along right side of KMP will be done at 100 Feet C/C. Minimum 07 No. observations will be taken in width for each X-section with Total station / DGPS instruments further superimpose on sajra (revenue record) along KMP. | Sealed quotation will be received upto 14:00 hours on 24.12.2021 & opened on 15:00 Hours same day. | 15000/- | 30 days |

Terms and conditions:

1. Earnest money will be deposited physically in the shape of Demand Draft in favour of Executive Engineer, Construction Division No.31, Gurugram.
2. No compensation shall be paid to the contractors for any damage due to natural calamity.
3. Payment will be released after completion of work in all respect.
4. Tracking of GTS stone within 10 KM. left and right side of site of proposed Mewat Feeder Canal with reference to latitude and longitude.
5. Survey shall be done from the permanent GTS benchmark and ended /closed thereto.
6. The firm shall be solely responsible for the accuracy of the survey.
7. Topography of existing structure (trees/ electric line/ parallel canal/ KMP X-ing/ NH X-ing/ Aquaduct etc.)with total station / DGPS instruments preparing computerized drawing showing all levels, dimensions and angles.

8. Preference will be given to firm/ agency who has completed the similar nature of work in government department.
9. No extra payment shall be made to firm /agency for the obstacles arising due to standing of water flooded area/ weed growth/ bushes/ trees/ mud/etc during survey.
10. Surveying instruments including surveyor/labour will be arranged by the agency/ firm itself.
11. Quotation will be submitted in the office of Executive Engineer, Construction Division No. 31, Canal Colony, Gate No.1, Sector-16, Gurugram, for more information Contact No.:0124-4009878, Mobile No. 7678215783.
12. Rates to be quoted including all taxes/GST.
13. Work shall be executed as per Haryana PWD specification and approved drawings.
14. Level Book to be submitted shall be in the format provided by Engineer-in-Charge.
15. Vertical control/permanent bench mark should be established by connecting at least 3 GTS stone at NCR, GWS Crossing near badli, Railway X-ing at RD 66.285 KM and at RD 72.434 KM and at RD 99.045 KM of KMP.
16. Temporary benchmark shall be established to nearby pucca structure along right side of KMP by mentioning location on topographical plan.
17. Preparation of topographical plan of site of proposed alignment for Mewat Feeder Canal alongwith structure showing all the details like trees/ electric line/ parallel canal/ KMP X-ing/ NH X-ing/ Aquaduct / Gas & fuel pipe lines and other utilities etc.
18. No quotation shall be entertained after due date/time.
19. **Sealed quotation of this work has been kept alive being single quotation received previously against this office Tender Ref. No.3117/8A dated 01.12.2021.**

Executive Engineer,
Construction Division No.31,
Gurugram.

Quotation Inviting Authority: Executive Engineer Construction Division No.31, Gurgaon

Name of Work: Topographical Survey for Mewat Feeder Canal Project off-taking from GWS Canal(50.600KM) along KMP Expressway (Right side) to near Nuh Disty., at Khor Basai

Contract No:

| | |
|-----------------------------------|--|
| Rate quoting agency name : | |
|-----------------------------------|--|

PRICE SCHEDULE

| Sl. No. | Item Description | Units | BASIC RATE In Figures To be entered by the agency Rs. | BASIC RATE In words To be entered by the agency |
|----------------|---|--------------|--|--|
| 1 | Carrying out complete survey work for Observing & plotting of L-sections, X-sections & topography of MFC including existing structure along right side of KMP will be done at 100 Feet C/C. Minimum 07 No. observations will be taken in width for each X-section with Total station / DGPS instruments. Further superimpose on Sajra (revenue record) along KMP. | 1 Job | | |
| | Note: Including all taxes. | | | |

Sign with seal of Agency